E.E. Reed Construction, L.P. Pricing Sheet

	PCO#	10
	PROJECT:	Service Center East
	DATE:	July 12, 2018
SUBJECT: Reroute the water line @ Q-Hut		

NO. DESCRIPTION		CRIPTION QUANTIT		TY LABOR		MATERIAL		SUBCONTRACT		TOTAL
NO.				UN.	AMOUNT	UN.	AMOUNT	UN.	AMOUNT	
				OIV.	AWOUNT	OIV.	AWOUNT	OIV.	AWOUNT	
1	Royal Restrooms	1	ls					2,167	\$2,167	\$2,167
2	HGA & CCI design costs		ls					2,870	\$2,870	\$2,870
3	Clifton Construction per attached		ls					13,731	\$13,731	\$13,731
4	·							,	. ,	
5										
	SUBTOTAL								\$18,768	\$18,768
	TAXES	7.00%							. ,	,
	WORKMENS COMP.	36.00%								
	SUBTOTAL									\$18,768
	INSURANCE	0.72%								\$134
	BUILDER'S RISK									
	SUBTOTAL									\$18,902
				-						
	GENERAL CONDITIONS	5.00%								\$945
FEE 5.00%									\$992	
	SUBTOTAL									\$20,840
							1			
	Sub Guard	1.50%								\$313
TOTAL										\$21,152



PCO #10 new Water line at Q-Hut

Narrative

During removal of topsoil just south of the Quonset Hut, we disturbed the unmetered water line running to the Q-Hut. It is only 8" below the surface. The line was not shown on the airport as-built drawings and was not discovered by the utility locator that came out on two (2) separate occasions by two (2) different contractors (Coleman Companies, Inc. & Georgia 811).


The line ties into a 5" Transite (asbestos) line that runs north to south directly under the new building (see attached).


We put a number of options through to the City of Savannah. All but one involved connecting to Transite pipe. The City would not approve connecting to the Transite. They have approved the attached drawing for running the water line from the Q-Hut.

The new work consists of the following:

- Design, several meetings and submissions to the City of Savannah by the civil engineer (Coleman Company). Hughes Group Architects is responsible for verification, coordination and issuance of drawings.
- 8"x2" sleeve & ball valve in box.
- 2" RPZ and set 2" meter & box.
- 492 If of 2" water service and fittings.
- Connection to existing 6" line with hydrant.
- Temporary toilets (Royal Restrooms) were put in place when the water line was disturbed because without water the Q-Hut did not have use of their restrooms.

Due to the fact that the line was not shown on the airport as-built drawings and that it was not discovered by the utility locate companies, we feel that this is an unforeseen condition. Also, the City of Savannah will not let us repair the line and is requiring us to run a new water line, we consider this a change in scope and are requesting a change order for this work.





2

3

4










	REVISIONS								
MARK		DATE		ISSUE					
1	4/1	8/201	8	SEE COVER SHEET					
ISSUANCES									
DATE	<u> </u>	IS	JANCE						

UTILITY PLAN

C-004.1

DATE: 4/12/2018 BY: TGB

Copyright 2013 © Hughes Group Architects



INVOICE

Date	Invoice #
5/10/2018	7947

Bill To	
Gulfstream South Facilities Krista Horne	
500 Gulfstream Rd Savannah, GA 31408	

	Rep	P.O. No.	Te	erms	Due Date
	KM		N	et 30	6/9/2018
D	· ,	QTY	Rate	Amount	
Booking #5053 Emergency Rental - Water O	utage at Bldg 1005	,			
Two-Stall Royal Restrooms: May 1 - 8, 2018 Fresh Water Fill			1 1	1,950.00 75.00	1,950.00T 75.00T
Please make checks payable to Royal Restroo Savannah, GA 31416. Thank you for choosing Royal Restrooms!	ms, LLC and remit	t to PO Box 13605,	Subtotal Sales Tax	(7.0%)	\$2,025.00 \$141.75
, , , , , , , , , , , , , , , , , , , ,			Total		\$2,166.75
Customer Signature & Date of Receipt			Payments/ Balance		\$0.00 \$2,166.75

Phone #	Fax#	E-mail	Web Site
912.234.6800	912.964.1228	kym@royalrestrooms.com	www.royalrestrooms.com

David Freitas

From:

Horne, Krista < krista.horne@gulfstream.com>

Sent:

Friday, May 11, 2018 1:28 PM

To:

David Freitas; Jacob Rakosi

Cc:

Steele, Sheila; Amy Rowland; Whalen, James

Subject:

Invoice 7947 from Royal Restrooms, LLC

Attachments:

Inv_7947_from_Royal_Restrooms LLC 5172.pdf

Hey David and Jacob ... per Jim Whalen please include the attached Royal Restroom Invoice 7947 in with the change order for the water pipe rework.

Thanks,

Krista Horne **Gulfstream Aerospace Corporation**

Real Estate Project Manager II

Cell: (912) 433-3352

From: kym@royalrestrooms.com [mailto:kym@royalrestrooms.com]

Sent: Thursday, May 10, 2018 4:22 PM

To: Horne, Krista < krista.horne@gulfstream.com> Subject: Invoice 7947 from Royal Restrooms, LLC

Royal Restrooms, LLC

Invoice Due:06/09/2018

7947

Amount Due: \$2,166.75

Hello Krista,

Thank you for your assistance today regarding the Royal Restrooms rental at 1005 LP Owens Dr. Attached is your invoice for the restroom rental. Please let me know if you have any questions, and I'll be happy to assist you.

We appreciate your business and the opportunity to serve you all at Gulfstream.

Sincerely,

Kym McCarty Royal Restrooms, LLC 912.234.6800 Office



June 30, 2018

Mr. Curtis Rakosi Vice President EE Reed Construction, LP 7505 Waters Avenue, Suite B8 Savannah, GA 31406

RE: Gulfstream Service Center East
Q-Hut Waterline Additional Services Request

Dear Curtis:

Our Civil Engineer, Coleman Company Inc., has incurred Additional Services due to the additional engineering required to for the Q-Hut Water Service. Attached is Coleman's hourly invoice dated June 30, 2018 which itemizes those requests. Below is the request for your consideration:

• Q-Hut Water Service:

HG Architects
 Coleman Company, Inc.
 Sub Total
 \$2,495

Total \$2,870

We look forward to continuing this project with you; please contact me if you have any questions.

Sincerely,

Amado Fernandez, AIA

Principal

cc: Jeff White April Bethune



Hughes Group Architects 22630 Davis Dr., Suite 175 Sterling, VA 20164

Invoice number

83370

Date

06/30/2018

Project 15-271 GULFSTREAM SERVICE CENTER EAST, DAVIDSON DR

Billing Through June 30, 2018 Tax ID: 80-0907863

Services:

- Onsite meetings with City of Savannah and EE Reed
- Meetings with City of Savannah Water and EE Reed
- Correspondence
- Plan Revisions
- Permitting

Professional Fees

		Hours	Rate	Billed Amount
CADD Technician				
Dillon C. Powell				
Project Time		4.00	75.00	300.00
Civil Project Manager / CFO				000.00
Gregory J. Coleman				
Project Time		14.00	130.00	1,820.00
Vice President / Professional Engineer / Project Manager				,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
Travis G. Burke				
Project Time		2.50	150.00	375.00
	Professional Fees subtotal	20.50		2,495.00

Invoice total

2,495.00

Aging Summary

Invoice Number	Invoice Date	Outstanding	Current	Over 30	Over 60	Over 90	Over 120
83370	06/30/2018	2,495.00	2,495.00				
	Total	2,495.00	2,495.00	0.00	0.00	0.00	0.00

CCI File No.: 15-271,000 Page 2 If these terms and conditions are acceptable, please sign below and return the original to this office. Thank you for the opportunity to submit this proposal and please call us if you have any questions or comments. Sincerely, Coleman Company, inc. Greg Coleman CFO/Project Manager GC/sawr **ACCEPTANCE OF PROPOSAL** The undersigned Contracting Party expressly accepts, consents, and agrees to the terms, fees, specifications, and conditions stated in the above Proposal. Payment will be made as outlined above. Name of Contracting Party: By (Signature): Date: _____ Print Name:

Gulfstream Service Center East - Quonset Hut Water Lateral

Davidson Drive, Savannah, Georgia



PO Box 7003 * 18 Gulfstream Rd. * Savannah, Ga. 31418 912-964-0366 Main * 912-964-1435 Fax * cliftonconstruction.com

912-964-0366 Main * 912-96	4-1435 Fax * clif	tonconstr	uction.com				
Change	Order Request						
Submitted to: David Freitas	Date:	Date Submitted: May 11, 2018					
Principal/Owner: EE Reed Construction L.P.			Gulfstream SCE				
Address: 705 Waters Ave.		Request #:					
City, State, Zip: Savannah, GA 31406		•	1000 Davidson D	r. Savannal	n, GA 31408		
Phone No: 571.641.0304			dfreitas@eereed.co		<u>·</u>		
Clifton Construction, Inc. proposes to perform the Work described below in accordance with industry standa page, when it is accepted by the Principal/Owner and approved as a contract by Clifton Construction, Inc.	rd practices. This proposal will I	become a contrac	- t, subject to the Standard Pr	rovisions and Conc	litions on the next		
Description of Work	Quantity	U/M	Unit Price	Τ	Total		
Wobilization	1	LS	\$352.24	\$	52,24		
Engineering/Layout	1	LS	\$171.73	\$1	171.73		
8"X2" Sleeve & Ball Valve In Box	1	EA	\$1,204.62		204.62		
2" RPZ	1	EA	\$1,835.19		835.19		
Set 2" Meter & Box (Owner Purchase Meter)	1	EA	\$2,251.85		251.85		
Directional Bore Under Pavement	50	LF	\$27.84		392.00		
2" Water Service	492	LF	\$10.43		131.56		
2" Misc. Fittings	1	LS	\$351.49		351.49		
Connect to Existing 6" Line to Hydrant	1	EA	\$1,392.32		392.32		
Connect to Existing of Entre to Hydrant		JEA .	TOTAL	\$	14,083.00		
			TOTAL				
NOTES:				_	<u>\$352.24)</u> 13,730.76		
The 4" main we are to tap is assumed to be PVC. Verification is in process. I	Price may change if 4"	line cleeve i	e an unusual fitting		13,730.76		
The 4 main to die to tape to assumed to be 100 formulation is in process.	i noc may onange n 4	inic biccvc i	s un unusuul nung.				
SPECIAL PROVISIONS:							
Payment terms: Net 30 owner funding not withstanding.							
Certified WBE w/ City of Savannah and GDOT -	- DBE						
•							
Clarifications:							
We directional boring is included:							
Replacement of asphalt and concrete is not included. Area is to be topped with a	tished concrete from on	site. <					
Utility location costs by a private locator service, if required, are additional.							
Staking & traffic control is included for Clifton scope of work only.							
Sincerely,							
Clifton Construction	ACCEPTANCE	:					
By Frank Trent	Ву						

Frank Trent Project Manager Date____